

Toll Free 1-800-493-5446

Physical Demands Analysis

T-Bar Installer

Prepared for: Alberta Construction Association

Job Title:	T-bar Installer	Assessment Location:	Grande Prairie, AB	Data Collection Date:	December 9, 2020				
Completed B	y: Christina O'Connor	, B. Sc. Kin.	Submitted on: July 29, 2021						
Disclaimer: The physical demands noted in this report may vary depending on company and location. Proceedings of contact the company directly to confirm this Physical Demands Analysis is an accurate representation of the specific job title for this specific location.									
Work Schedule:	Shift Duration: 4 days/week, 10 hours/day; may vary Break Schedule: Total of 1 hour break per day/ extra ½ hour past 5:30pm Shift Rotation: This would be job-dependent; however, if working on commercial jobs, workers may be required to work at night to avoid working during business operation hours. On call is required: No. Overtime required: Yes, this would be job dependent.								
Education / Experience:	Hours required for Tickets that may I Ground Disturbance	Education required: N/A Hours required for position: N/A Tickets that may be required (not limited to): Fall protection, H2S Alive, Wildlife awareness, Ground Disturbance, Elevated Work Platform (EWP) machinery use, Confined Space, First Aid, WHMIS, Construction Safety Training Systems (CSTS) and Basic Safety Orientation (BSO).							
Labour Provider:	N/A	N/A							
Job Overview		A T-Bar Installer is required to determine the square footage required using various handheld tools and to ensure all materials placed are level. A worker would be required to map out							

lighting required, and to ensure ceiling tiles evenly spaced.							
% of shift	Job Task	Task Description					
2%	Paperwork	A worker would be required to fill out their Field Level Hazard Assessment (FLHA), COVID screening paperwork, toolbox talks, and equipment inspection forms. A worker would be required to fill out multiple toolbox talks and field level hazard assessments if a job changes throughout the day.					
5%	Clean Up / Job Prep	A worker would be required to prepare their job site by gathering all tools and equipment necessary to complete the tasks at hand, gathering all materials, ensuring proper PPE, and setting up any temporary containments.					

sections to ensure main Ts and cross Ts are placed correctly to allow for any venting and

Date Prepared: January 8, 2021 Prepared for: Chinook Drywall



		A worker would be required to clean up throughout their day to reduce any materials or equipment that could impact a worker's ability to complete a job. A worker would be responsible for cleaning up their tools and materials to ensure there are no safety hazards throughout their day.
93%	T-bar installation	A worker would be required to determine the square footage required using various handheld tools and to ensure all materials placed are level. A worker would be required to map out sections to ensure main Ts and cross Ts are placed correctly to allow for any venting and lighting required, and to ensure ceiling tiles evenly spaced.

Eq	uip	m	en	t/
To	ols	:		

- Ceiling tiles (60 lbs)
- Main Ts (50 per box, 100 lbs)
- Cross Ts (20 per box, 60 lbs)
- Wall mold (64 lbs)
- Screws
- Snips
- Hilti concrete nailer (10 lbs)
- Lasers
- Scaffolding (46 lbs for deck, 42 lbs for railings, bar 16 lbs)
- Ladder (45 lbs)
- Tape measure

Exposures / Environment:

Work can be inside or outside depending on the jobs required. A worker could be exposed to the following:

- Noise
- Rough Terrain
- Tripping Hazards
- Moving Equipment
- Heights
- Vibrations
- Hot/Cold Temperatures
- Dust

Personal Protective Equipment Required:

- Hard hat
- Steel toed boots
- Gloves
- Foam safety eyewear (fectoggle)
- Safety vest or high visibility stripes
- Long sleeves and pants

Date Prepared: January 8, 2021 Prepared for: Chinook Drywall



Personal Protective Equipment as Required:

Hearing protection

NOC STRENGTH LEVEL KEY						
Strength Level Definition						
Limited (Lim)	Up to 5 kg (11 pounds)					
Light (L)	5 kg to 10 kg (11 – 22 pounds)					
Medium (M)	10 kg to 20 kg (22 – 44 pounds)					
Heavy (H)	Greater than 20 kg (44 pounds plus)					

^{*}Strength Level Key based on the National Occupational Classification

FREQUENCY KEY									
Frequency	% of Workday	Hours – Based on 8 hour Workday							
Not Required (N/R)	0%	0							
Rarely (R)	1-5%	<25 min/day							
Occasionally (O)	6 – 33%	25 min to 2 hours 40 min/day							
Frequently (F)	34 – 66%	2 hours 41 min to 5 hours 17 min/day							
Constantly (C)	67 – 100%	5 hours 18 min to 8 hours/day							

*Frequency Key based on WCB Alberta Recommendations

Job Demand	Frequency / NOC Strength Level					Details/ Measurements			
	N/R	R	0	F	С				
Material Handling:	Material Handling:								
Floor to waist level lifting		н		Lim		Could be required to lift the following from ground level: A variety of tools and equipment A bundle of cross Ts (60 lbs) A bundle of main Ts (100 lbs) A cross T (3 lbs) A Main T (2 lbs) Hilti concrete nailer (10 lbs) A box of wall mold (64 lbs) Scaffolding deck (46 lbs) Scaffolding railings (42 lbs) Scaffolding bars (16 lbs)			
Knee to waist level lifting			Н			Could be required to lift the following from knee level: Bench (13 lbs) Ladder (45 lbs) Hand tools (5 lbs) A bundle of cross Ts A bundle of main Ts			

Date Prepared: January 8, 2021 Prepared for: Chinook Drywall



Waist to waist level lifting	Н	Lim		Could be required to lift the following from waist level: A bundle of tiles Wall mould (64 lbs) Cross Ts (60 lbs) Main Ts (100 lbs) A cross T (3 lbs) A Main T (2 lbs) Hand tools
Waist to chest level lifting	н	Lim		Could be required to lift the following to chest level: • A bundle of tiles onto the scaffolding (60 lbs) • A wall mold (<5 lbs) • A cross T (3 lbs) • A Main T (2 lbs) • Hand tools • Laser
Waist to shoulder level lifting	Н		Lim	Could be required to lift the following to shoulder level: • A bundle of tiles onto the scaffolding (60 lbs) • A wall mold • A cross T (3 lbs) • A Main T (2 lbs) • Hand tools • Concrete nailer (10 lbs) • Laser
Waist to overhead level lifting			Lim	Could be required to lift the following overhead: • A cross T (3 lbs) • A Main T (2 lbs) • A single ceiling tile (10 lbs) • Clamp • Hand tools • Laser
Front carry	н			Could be required to carry the following: A bundle of tiles A bundle of cross Ts A bundle of main Ts A ladder Bench

Date Prepared: January 8, 2021 Prepared for: Chinook Drywall



Right / left-handed carry (dominant hand)		Lim		Could be required to carry the following: Tools Hilti Bench A cross T (3 lbs) A Main T (2 lbs)
Shoulder carry	Н			Could be required to carry the following on their shoulder: • A bundle of tiles • A bundle of main Ts • A bundle of cross Ts This would be worker dependent if they to chose to carry on their shoulder.
Static Pushing/Pulling (Force)			Lim	Pushing and pulling would be required with use of a drill, when assembling scaffolding, when drilling, when putting in rivets, when connecting cross Ts and main Ts, etc.
Dynamic Pushing/Pulling (Force)		М		Required when moving scaffolding, opening/closing doors, sweeping, moving materials, etc.

Job Demand		F	requenc	Су		Details/Measurements
	N/R	R	0	F	С	
Upper Extremity Work:						
Hand Gripping				Х		Required when using a Hilti nailer, using a
						ladder, removing scaffolding, installing T-bar
						ceiling, clean up, site prep, etc.
Pinch Gripping			Х			Required when using tools, when cutting main
						Ts and cross Ts, when measuring, when
						screwing in materials, when using rivets,
						completing paperwork, etc.
Upper Extremity					Х	Required when doing site prep, during site
Coordination						cleanup, when assembling T-bar ceilings, using
						tools, getting materials, etc.
Reaching Forward			Х			Required when doing site prep, during site
						cleanup, when assembling T-bar ceilings, using
						tools, getting materials, etc.
Overhead Shoulder Level				Х		Required when assembling the framework for
Reaching						T-bar ceiling, when measuring, when using a
						laser, when installing the T-bar ceiling, when
						installing the ceiling tiles, etc.
Below Shoulder Level			Х			Required during site cleanup, site prep,
Reaching						gathering materials, prepping materials,
						measuring materials, etc.

Date Prepared: January 8, 2021 Prepared for: Chinook Drywall



Throwing X Required when tossing garbage into bins.

Job Demand		Fi	requenc	у		Details/Measurements
	N/R	R	0	F	С	
Positional Work:						
Trunk Flexion (Bending)			Χ			Required when completing site cleanup, site
						prep, gathering materials, cleaning up any
						debris, etc.
Trunk Rotation (Twisting)			Х			Required when completing site cleanup, site
						prep, gathering materials, cleaning up any
						debris, installing T-bar ceiling, working at
						heights, etc.
Kneeling		Х				Required when working in awkward spaces or
						when working on scaffolding.
Crawling		Х				Required if working on scaffolding in awkward
						positions.
Crouching		Х				Required when working in awkward spaces or
						when working on scaffolding.
Squatting		Х				Required when working in awkward spaces or
						when working on scaffolding.
Neck Flexion			Х			Required when gathering materials, site
						cleanup, site prep, measuring materials,
						cutting materials, etc.
Neck Extension					Х	Required throughout the day when working
						overhead to install a T-bar ceiling, to install
						tiles, to measure, to secure ceiling, etc.
Neck Rotation			Х			Required throughout the day as a safe work
						practice as well as when installing T-bar ceiling,
						measuring, cutting, etc.

Job Demand		F	requenc	у		Details/Measurements				
	N/R	R	0	F	C					
Static Work:	Static Work:									
Sitting			Х			Required on breaks, driving to site, and				
						completing paperwork.				
Static Standing				Х		Required when completing work on ladders,				
						scaffolding, or step ladders.				
Balancing				Х		Required when completing work on ladders				
						and scaffolding.				

Job Demand	Frequency					Details/Measurements
	N/R	R	0	F	С	
Ambulation:						
Walking: Level Surfaces				Х		This is job dependent, however most jobs are typically on even ground at this stage.

Date Prepared: January 8, 2021 Prepared for: Chinook Drywall



Walking: Uneven		Χ		Required when walking outside on various
Surfaces				job sites.
Walking: Slopes		Х		This would be site dependent.
Jumping	Х			N/A
Running	Х			N/A

Job Demand		Frequency				Details/Measurements	
	N/R	R	0	F	С		
Climbing:							
Stairs		Х				This is site dependent. Stair climbing may be required more on one site than another.	
Ladder			Х			Required when completing T-bar installation; however, this could be interchangeable with the use of scaffolding.	
Other			Х			Required when completing T-bar installation; however, this could be interchangeable with the use of ladder climbing.	

Date Prepared: January 8, 2021 Prepared for: Chinook Drywall



PHOTOS OF TASKS AND WORK ENVIRONMENT

Figure 1: An example of what a room may look like prior to installing a T-Bar Ceiling.



Figure 3: A worker installing a main T onto the wall and ensuring all angles are right.





Figure 2: A worker would use a laser to ensure all wall molds are placed level to one another.



Figure 4: A section of the suspended ceiling that was completed. The Main T is running length wise, while the Cross Ts are running horizontally.



Date Prepared: January 8, 2021 Prepared for: Chinook Drywall



If you have any questions, and/or would like to discuss this assessment and report further, I can be reached at (780) 532-7077.

Sincerely,

Christina O'Connor, B. Sc. Kin

Date Prepared: January 8, 2021 Prepared for: Chinook Drywall



Validation Agreement

Job Title:	T-Bar Installer
Data Collection Date:	December 9, 2020

We the undersigned have reviewed the Physical Demands Analysis for this position and agree that the physical demands documented in this report are representative of the true demands of the tasks associated with the job title as assessed on the date listed above.

Completed by:	Christina O'Connor, B. ScKin	Lifemark Clinician Name and Designation
Approved by:		Management Representative
Approved by:		Worker Representative
Approved by:		Labour Provider Representative